TAYLOR AND KNOWLES BESPOKE BUILDING PTY LTD

BLOCK 16 SECTION 7, **FORREST**

17/1270




ISSUE DATE: 11.08.2017 ISSUE: NCA WORKS APPROVAL REVISION: A

DRAWING SCHEDULE

LANDSCAPE DRAWINGS:

DWG No. Drawing Title L501.1 LANDSCAPE PLAN L501.2 PLANTING PLAN

L501.3 LANDSCAPE FINISHES, FIXTURES AND MATERIALS L501.4 LANDSCAPE MANAGEMENT AND PROTECTION PLAN



DRAWING STATUS
Warning unless there is an authorised SPACELAB signature in the approved for issue column, this drawing is not approved for issue.

COPYRIGHT
This drawing remains the property of SPACELAB Studio It may be used for the purpose for which it was commissioned & in accordance with the terms of engagement for that commission. Unauthorised use of the drawing is prohibited.







41 NATIONAL CIRCUIT, FORREST - LANDSCAPE FINISHES SCHEDULE PLAN REFERENCE COLOUR, SIZE & FINISH SUPPLIER WEE JASPER STONE 0439 117 405 MATERIAL: WEE JASPER BLUESTONE FLAGGING SIZE: CRAZY PAVE PATTERN MIN. PIECE SIZE 300mm, 30-50mm T FINISH: NATURAL PAVEMENT TYPE 1 UNIT 1 & 2 ENTRY PAVING PT1 www.weeiasperslone.com AMBER TILES COLOUR: BRAVE 'COKE' PAVEMENT TYPE 2 UNIT 1 & 2 ALFRESCO PAVING 1300 139 868 www.ambertiles.com.eu PT2 SIZE: 600x600x10mm FINISH: NATURAL AMBER TILES 1300 139 868 www.ambertiles.com.au PAVEMENT TYPE 3 UNIT 3 ENTRY AND ALFRESCO PAVING COLOUR: BRAVE 'EARTH' SIZE: 600x500x10mm FINISH: NATURAL PT3 AMBER TILES 1300 139 868 www.amberiles.com.au PAVEMENT TYPE 4 UNIT 4 ENTRY AND ALFRESCO PAVING COLOUR: BRAVE 'PEARL' SIZE: 600x600x10mm FINISH: NATURAL

41 NATIONAL CIRCUIT, FORREST - LANDSCAPE FIXTURES SCHEDULE						
PLAN REFERENCE	ITEM	COLOUR, SIZE & FINISH	SUPPLIER			
FT1	UNIT 1 &2 FENCING	MATERIAL: POWDERCOAT STEEL POSTS, PVC COATED WIRE SIZE: 1000mm H, 300mm W GATES TO MATCH COLOUR: BLACK	THE FENCING STORE T 1300 530 306 www.fisfencingstore.com.eu			
FT2	UNIT 3 & 4 FENCING	MATERIAL: KWILA HARDWOOD SIZE: ROX19mm BOARDS, 1800MM H, STEEL POSTS AT 3m CTRS, POWDERCOAT BLACK 900mm W GATES TO MATCH	SUPPLIER TO BE NOMINATED BY CONTRACTOR FOR APPROVAL BY THE SUPPRINTENDENT PRIOR TO ORDERING.			
FT3	SITE BOUNDARY FENCING (LAPPED AND CAPPED)	MATERIAL: TREATED PINE SIZE: 1800mm H - 100x16mm PALINGS, 75x50mm CROSS RAILS x3, 75x50mm CAPPING, 150x50mm POSTS	SUPPLIER TO BE NOMINATED BY CONTRACTOR FOR APPROVAL BY THE SUPERINTENDENT PRIOR TO ORDERING.			
LG1	WALL LIGHT "ALICE"	MATERIAL: ANODIZEO ALUMINIUM, LED SIZE: 85mm W x 128mm H x 60mm D COLOUR: LED GLOBE: WARM WHITE	VERSALUX T (02) 9922 8900 www.versalux.com.au			
BT1	GARDEN BOULDERS	MATERIAL: NATURAL BASALT SIZE: VARIES MAX 1000mm Ø, MAX 450mm ABOVE ADJACENT SURFACE NOTE: BOULDERS TO BE	WEE JASPER STONE 0439 117 405 www.weejasperstone.com			
NA	CLOTHESLINES	SIZE: 2200mm L x 1200mm D MATERIAL : POWDERCOAT ALUMINIUM (COLOUR TBC) NOTE: WALL MOUNTED, FOLDING	HILLS 1300 305 564 www.nilshome.com.au			

EDGE

EXISTING BRUSHWOOD FENCE TO BE RETAINED

PLANTING

DRIVEWAY (RAMP DOWN)

MATERIALS IMAGES




LG1 - Wall Mount Light

PLANTING

1000mm HIGH BLACK CYCLONE MESH-FENCING ATOP STONE RETAINING WALL

FT1: 1000mm Transparent Fencing FT2 - 1800mm Timber Fencing

UNIT 1 FENCING COURTYARD



BT1 - Boulder retained garden bed



PT3 - 600x600mm 'Earth' Tile

FT3 - 1800mm Site Boundary Fencing

Clotheslines - Wall mounted



PT4 - 600x600mm 'Pearl' Tile





Betula papyrifera

PLANTING IMAGES

Prunus 'Sekiyama'

Pyrus calleryana 'Capital'









Quercus coccinea

Zelkova serrata 'musashino'

Pittosporum 'Green Pillar'

Photinia 'Red Robin'







Viburnum odoratissimum 'VOC1' Acacia cognata 'mini cog'

Agapanthus 'White Dwarf'









Dichondra repens

Casuarina glauca 'Cousin It' Grevillea juniperina Hebe buxifolia









Liriope 'Just Right'

Lomandra longifolia 'Tanika' Phormium tenax 'Flamin'

Trachelospermum jasminoides

NOT FOR CONSTRUCTION

AS SHOWN

1 INDICATIVE DRIVEWAY SECTION SCALE 1:20 @ A1 1:40 @ A3

STONE RETAINING WALL

SCREENING HEDGING

TO BOUNDARY

5 mg





STONE RETAINING WALL






41 NATIONAL CIRCUIT B16, S7 FORREST, ACT

LANDSCAPE FINISHES, FIXTURES AND MATERIALS

17/1270 L501.2 NCA



LEGEND

PROPERTY BOUNDARY

TREE TO BE RETAINED Fence tree as detailed



TREE TO BE REMOVED

TREE PROTECTION ZONE TREE PROTECTION FENCING



Refer to Tree Protection Conditions NEW DRIVEWAY/VERGE CROSSING Refer Civil Drawings

TREE NUMBER AS PER CANOPY REPORT

NOTE: REFER CANOPY ARBORICULTURAL REPORT FOR DETAILS ON TREE SPECIES, QUALITY, HEALTH AND RETAIN/REMOVE RECOMMENDATIONS

TREE PROTECTION CONDITIONS

STANDARD CONDITIONS

- A copy of these conditions shall be kept on site from the time that the protective fences are erected to the time that all works are completed on site.
- Tree removal All protected trees are to be retained unless otherwise stated in Specific Conditions below
- Fencing of protected trees • 1800 mm high chain wire protective fence at the extent of the tree protection zones as identified in the
- The protective fences shall be erected prior to the commencement of any earthworks, construction or demolition activity on any part or stage of the development and shall remain in place until all construction works are completed.
- The protective fence shall be maintained in good order for the duration of the construction works.
- A Tree Protection Sign, as specified by Environment ACT, shall be prominently displayed on the fences of all fenced off areas.

- No activities permitted within the fenced off area

 No activities are permitted in the fenced off area unless otherwise stated in Specific Conditions below.
- Tree surgery will be permitted to trees requiring such action. Activity is to be undertaken in accordance with AS 4373 by a qualified arboriculturist to ensure that the activity results in a balanced tree.

SPECIFIC CONDITIONS

- Protective Fencing

 Protective fencing is to be erected and maintained in accordance with the Standard Conditions except for trees included on the drawings that are affected by works adjacent to trees. These trees are to be fenced to the tree protection zone with the exception of the area identified as 'affected' and may include a 1 metre buffer area to allow works to occur
- For the purposes of these conditions, the area inside the protective fencing is referred to as the 'fenced off

Only trees that have been endorsed within the Canopy Report and the Landscape Management Protection Plan as marked for removal may be removed. Services

- Services and Utilities reticulation is permitted in accordance with the following conditions:
- Works under the Canopy extent must be undertaken by underboring.

 Works within the Tree Protection Zone but outside the drip line must be undertaken by hand excavation.

 No roots greater than 50mm in diameter are damaged; and
- Are at the minimum depth provided by the relevant Standards or Authority requirements.

Low Impact Works

Low Impact activity may occur within the fenced off areas of trees (other than Registered Trees and those classified as being of 'Exceptional' quality) for the purpose of "light works", which includes the constructing footpaths, bike paths, driveways, swale drains, specific footing, garden beds and the like, provided the activity is in accordance with the following conditions:

- The cultivation of soil for irrigation and shrub beds is not considered a groundwork activity provided it is in accordance with the limitations below
- . Generally, no activity occurs within 3 metres of the trunk, with the exception of landscaping activities specified below. Garden beds, where within 3 metres of the trunk must be no greater than 300mm in depth, excavation is
- limited to 50mm and where the garden beds adjoin a tree, a gravel breathing layer is used.

 Fences and walls within the drip line and more than 3 metres from the trunk will not be allowed unless
- piers are used at 2.5m centre. No strip footings permitted.

 Any soil required for landscaping and irrigation purposes adjacent to trees must not be excavated below 50mm and result in fill which would exceed the natural surface level by 100mm.
- Generally, excavation is limited to a depth of 150mm below natural ground level, except where it may be specified within the specific conditions.
- No roots greater than 50mm in diameter are damaged;
- The excavated area for footpaths, swale drains, bike paths etc is less than 2.5 metres in width.
 Protective fences may be moved to provide sufficient space to allow footpaths, bike paths or swale drains to be constructed whilst continuing to protect areas not affected by the activity; and

 Where there are existing structures, paths and services, low impact works may be undertaken provided
- there is no increase in the development footprint and excavation is limited to a depth of 300mm below natural

Specific Tree Works

- Any tree works proposed need to be undertaken in consultation with a qualified arborist (with reference to AS4373), with the following specific measures in place:
- Works to commence in winter to ensure minimal setback to tree
 Any excavation within the drip line needs to be via a non-destructive method (eg hydo-vacuum)
- Any root cut needs to be managed by a qualified arborist, ensuring stability of tree is maintained
 Qualified arborist is to propose maintenance program post works to ensure healthy long term growth (eg watering, Seasol trreatment)
- Driveway reinforcement to be increased so that the concrete pavement can be reduced to 100 mm and base reduced to 75mm to help achieve the maximum 50mm excavation

 - Footpath levels to be raised above natural ground level adjacent to the two larger trees, addition of dowel
- joints between the concrete slabs of the footpath to reduce the likelihood of tree roots popping up individual slabs and causing trip hazards

 Any Failure to comply with the above conditions is an offence under the Tree Protection Act 2005 and may result in an infringement notice of up to \$1,000 for an individual or \$5,000 for a corporation. Prosecution of a more serious offence may result in a criminal conviction and a penalty of up to \$40,000 for an individual or a penalty of up to \$200,000 for a corporation.

LANDSCAPE MANAGEMENT NOTES

- 1.0 GENERAL NOTES:
- These drawings are to be read in conjunction with Architects and engineers drawings.
- 1.2 This plan is to be implemented in accordance with "City Management Guidelines for the Protection of Public Landscape Assets Adjacent to Development Works-REF-04"
- STORAGE OF CONSTRUCTION MATERIALS
- 2.1 No construction material to be stored inside protected areas. No car parking or equipment parking to be permitted inside protected areas.
- 3.0 SITE ACCOMMODATION
- 3.1 No site sheds, storage sheds, sile amenities or billboards to be erected inside protected areas. Advertising and signage to be located within property boundary.
- 4.0 LANDSCAPE RESTORATION
- The landscape must be restored to pre-development conditions. Any disturbance to be reinstated to match predevelopment conditions and species.
- 5.1 Use 1800mm tall temporary security fence for the protection of verge trees. Fencing to be erected on commencement of construction and removed at commencement of site restoratio

ALL WORKS TO BE CONSTRUCTED IN ACCORDANCE WITH: The A.C.T. Government's "Standard Specification for Urban Infrastructure Works" and the "Design Standards for Urban Infrastructure". Edition 1, Revision 0. September 2002.

NOT FOR CONSTRUCTION




SSUE FOR NCA

DRAWING STATUS
Warning unless there is an authorised SPACELAB
signature in the approved for issue column, this drawing
is not approved for issue
COPYRIGHT
This drawing invitants the property of SPACELAS Studio
it may be used for the purpose for which it was









	,,,,,,	011 0011011100110			
LANDSCAPE MANAGEMENT AND PROTECTION PLAN		0 2	4 6		
		1:200			
ROJECT No	DRAWING No.	ISSUE	REVISION		
7/1270	15014	NCA	Δ		